MESSAGE SCAN FOR EARL C. RUBY

To Earl C. Ruby: RO5F16A

From:

1Guest:RO5FO7D53A Postmark: Dec 17,93 10:09 AM

- The land

Previously read Urgent

Status: Subject: Reply to a reply: Narratives

Reply text:

From: 1Guest:R05F07D53A Date: Dec 17,93 10:09 AM ocops. forgot to send this...

Preceding message:

From: Earl C. Ruby: RO5F16A Date: Dec 17,93 8:46 AM

Yes. Please let me see the 2500-8 and narrative. I really want to see it, and I also want a copy to keep in my files. I collect all of those that I can find to use as background information for teaching and lectures.

Yes I also need the spec books for the blowers. I looked for that folder on my last day, but could not find it. I did not even THINK about asking you to help me look -- you had a sore eye and I felt for you so much that my eye hurt too.

The camera is Bob Bleckers. He gave it to me at fire camp, to use during the survey and rehab effort. Nice camera. I mailed all of the photographs yesterday. ecr

From: 1Guest:R05F07D53A Date: Dec 17,93 8:36 AM

I finished that 2500-8 for DEC. and sent it on to Bob. want to see it? I need to leave for about 30 min. or so so can send it and be back if you're going to be around. Also, I have your camera and those specs books for the blower I need to get to you.did you get that stuff in the mail (Gosh I hope so-its Friday.) I imagine you would have asked me about it if you hadn't

-----X======X=======-----

From: Earl C. Ruby:R05F16A Date: Dec 17,93 8:03 AM

Yes

From: 1Guest:R05F07D53A Date: Dec 16,93 4:13 PM Earl? You still around?

Rotale Salestal Water

2500-8 INTERIA

muse this the his

30 My 12016

Delivered: Dec 17,93 10:07 AM

A. Type of Report

Date of Report: __12/15/93

BURNED-AREA REPORT

(Reference FSH 2509.13, Report FS-2500-8)

PART I - TYPE OF REQUEST

	[x] 2. Accomplishment Report	nated FFFS-FW22 funds
В.	. Type of Action	
	[] 1. Initial Request (Best est rehabilitation measures)	cimate of funds needed to complete eligible
	[x] 2. Interim Report	
	<pre>[x] Updating the initial fu data and design analysi</pre>	anding request based on more accurate site
	[x] Status of accomplishmen	ts to-date
	[] 3. Final report - following	completion of work
	PART II - BUR	RNED-AREA DESCRIPTION
Α.	. Fire Name: MARRE	B. Fire Number: <u>CA-LPF-001254</u>
C.	. State: <u>CALIFORNIA</u>	D. County: SANTA BARBARA
Ε.	. Region: <u>5</u>	F. Forest: LOS PADRES
G.	. District: SANTA BARBARA / SANTA	LUCIA
Н.	. Date Fire Started: 9/25/93	_ I. Date Fire Controlled:10/11/93
J.	. Suppression Cost: \$21,000,000.	· _
К.	. Fire Suppression Damages Repaired	with FFFS-PF12 Funds:
,	 Fireline waterbarred (mil Fireline seeded (miles) _ Other (identify) <u>10 Drop</u> 	O Mi
L.	Watershed Number: 1806 001 002,	1806 001 003, 1806 000 802
М.	NFS Acres Burned: 29,629 To Ownership type: (8,068)State (none)BLM (

N.		nise, Grass-Oak Savanna, Ceanothus, nita Conifer Timber,Grass	
ο.	. Dominant Soils: DIAB	O, ALTAMONT, LODO, MILLSHOLM, SHEDD WITZEL	
P.	. Geologic Types: SEDI	ENTARY-SANDSTONE, SILTSTONE, SHALE, SERPENTI	NE.
Q.	. Miles of Stream Channel	by Order or Class:	
	<u> </u>	II = 15	23
R.	. Transportation System:		
	Trails: (mi	es) Roads: 30 (miles)	
	PAR	III - WATERSHED CONDITION	
Α.	. Fire Intensity (Acres):	14,754 (low) 7,869 (moderate) 20,577 (high)
В.	. Water Repellent Soil (A	res): <u>15,352</u>	
c.	. Soil Erosion Hazard Rat	ng (Acres):	
	0 (low)	(moderate) <u>43,201</u> (high)	
D.	. Erosion Potential: 91	tons/acre	
Ε.	. Sediment Potential:	8,505. cu. yds/sq. mile	
	PART I	- HYDROLOGIC DESIGN FACTORS	
Α.	. Estimated Vegetative Re	overy Period: 10 years. (From Rowe, et al Er	osion
В.	. Design Chance of Succes	: 90 percent. (Where homes potentially affe	cted)
c.	. Equivalent Design Recur	ence Interval: 100 years.	
D.	. Design Storm Duration: District)	24 hours (coincides with Rowe, et al & floo	d
Ε.	. Design Storm Magnitude:	12 inches (from NOAA atlas)	
F.	. Design Flow: 85 - 115	fsm.	
G.	. Estimated Reduction in	nfiltration: 40% percent.	
Н.	Adjusted Design Flow:	20 - 160 ofem	

C.	Probability	\mathbf{of}	Completing	Treatment	Prior	to	First	Major	Damage	Producing
	Storm:									

Land 85 % Channel 90 % Roads **70 %** Other 100 % (Early Warning)

D. Probability of Treatment Success

	<years< th=""><th>after treat</th><th>ment></th></years<>	after treat	ment>
_	1	3	5
Land			
	60%	75%	80%
Channel			
	80%	100%	100%
Roads			
_	70%	70%	100%
Other	·		
(Early Warning)	95%	95%	95%

Cost of No-Action (Including Risk):

\$34,742,316.

- Cost of Selected Alternative (Including Risk): \$28,591,602.
- G. Skills Represented on Burned-Area Survey Team ("x" appropriate boxes):
 - [x] Hydrology
- [x] Soils
- [x] Geology
- [x] Range

- [x] Timber [] Contracting [x] Ecology
- [x] Wildlife
- [x] Fire Mgmt. [x] Engineering

- [x] Botany
- [x] Fishery Bio. [x] Economist [x] Statistician
- [] Research
- [x] Archaeology

Team Leader: BOB BLECKER

Phone:

(805) 681-2763

DG Address:

B.BLECKER: R05F07A

Induly Dueslad?

PART VI - EMERGENCY REHABILITATION TREATMENTS AND SOURCE OF FUNDS BY LAND OWNERSHIP NOTE: Emergency rehabilitation is work done promptly following a wildfire and is not to

solve watershed problems that existed prior to the wildfire.

solve watershed problem	ms tha	t exis			e wild:	•	_ T T		T .	11 7 1
I down The control	TT* .	I T T		Lands	lou		Lands		A	11 Lands
Line Items	Units	1	4	FFFS-				Non-Fed		
		Cost	of	FW22	\$	of	SCS	\$		
		\$	Units	\$	S.B.	Units		CDF	T	otal
	I				Count	У	USFSt	ident.		\$
A. LAND TREATMENTS	1.	1 4 1. 1.	l	140-011	·		T	T	12	
Aerial Grass Seeding	Acres		7,940	\$350M					\$	350,000
Rice Straw Mulching	Acres	\$871	70	\$61,000					\$	61,000
+Straw Bale Deflectors	Each	\$2.9M	3				8,800	·	\$	8,800
+Aerial Seeding	Acres		137				4,150		\$	4,150
+Donated Grass Seed-CDF	Lbs	\$ 3	530				1,190	\$1,590		1,590
+Donated Grass Seed-USFS		\$ 3	560				1,680	Ψ1, 750	<u>φ</u>	1,680
+Earth Berm Deflector	Each	\$1.1M		Pro i M	l odifio	1 To St	<u> </u>	lector D	uni	
Earth Bern Berrector	Lacii	ΨΙ.ΙΝ	L4	Final				total	ur.T	427,220
B. CHANNEL TREATMENTS				rinar	Design	•	Sub	locai		427,220
Channel Clearing	Mi.	\$4M	2.75	\$11,000	I			,	\$	11,000
Willow/Straw Wattles	Miles	1	4.5	\$ 9,000		Delete	d Duri	ng Final		
Gradient control Struct	Each	\$100	100	\$10,000				ng Final		
				, , , , , , , , , , , , , , , , , , , ,						
+Channel Clearing Privat	Feet	\$ 20	600				11.8M		\$	11,800
:	•		*	······································		Subtota	Chan	nels	\$	22,800
C. ROADS AND TRAILS										•.
Winter Flood Patrol	Days	\$1.2M	20	\$24,000					\$	24,000
Culvert Clearing	Each	\$188	80	\$15,000	***************************************				\$	15,000
Clearing Ditches	Miles	\$6.7M	0.74	\$5,000					\$	5,000
Rip Rap Energy Dissipat			500	\$15M				٠	\$	15,000
Debris Racks		\$556	9	\$ 5M					\$	5 000
Trail Treatments	Mile	\$132	22	\$29M					\$	29,000
	*				Sul	ototal I	Roads		\$	40,000
					Sul	ototal 7	Trails		\$	29,000
D. OTHER EMERGENCY ACTIO	ONS									y-
Road Closures Gates		\$1.7M	3	\$ 5,000					\$	5,000
Early Warning System	Each	\$ 4M	1	\$ 2,000					\$	4,000
				, , ,					Ť	,,
E. BAER EVALUATION/ ADMI	NISTRAT	TIVE S	JPPORT	L	<u> </u>			,		
	Days		58	\$13,000					\$	13,000
Team Members	Days	225	320	\$72,000	:				\$	72,000
*Archaeology Support to			Ĭ						<u> </u>	
Implementation	Days	214	48	12,000					\$	12,000
Implementation Overhead	Days	250	60	44,000					\$	44,000
	1			,					Ť	,
F. TOTALS			5	663,000	\$2000		2643 0	1,590	\$	693,020
+Treatment to private lar	nd with	nin For	rest bou	ındary (d	co-op v	vith SCS	3).			

⁺Treatment to private land within Forest boundary (co-op with SCS).

^{*} Based on 4-26-88 Fire Recovery PA by RF. [48 days (\$12,000) for land-disturbing channel, gate road, and trail treatments, 152 days (\$63,000) for aerial seeding treatments.]

EMERGENCY TREATMENTS.

Treatments were directed at those flood hazard areas identified in the burned area survey, and associated down slope areas that could be damaged by runoff from the flood source areas. Cost adjustments reflect nearest estimate based on available cost documentation. Final report will be forwarded within 6 weeks.

A. LAND TREATMENTS.

- 1. <u>Aerial Seeding</u>. (7,940 Acres)

 Much of seeding operations were conducted using Helicopter 527 and crew. Daily availability rate of H-527 was covered by the Marre
- 2. Rice Straw Mulching (70 acres)
 Approximately 60 acres of candidate mulching sites were initially located and staked on the ground. Ten additional acres were identified on site as candidate areas and mulched accordingly.

Incident for reconn. activities, reducing cost to seeding project.

Logistical, personnel and supply needs were significantly underestimated.

3. Treatments on private property.

- a. Straw Bale Deflectors. (3)
 Three straw bale structures, 200 feet long and approximately 3
 feet high were constructed. Implementation of this treatment was underestimated RE: logistics and personnel needs.
- b. Earth Berm Deflector. During the design phase it was found that the soils onsite were not capable of being compacted sufficiently to make a safe structure. Therefore, it was determined that a straw bale deflector would be more reliable and achieve the same objective. The SCS representative, agreed with this change in type of structure.
- c. Grass Seeding. (137 acres)
 All of the 137 acres of private land were seeded with Blando
 Brome grass, at a rate of 8 pounds per acre. Forest Service
 estimates were offset by seed donations and application by fixed
 wing aircraft.
- d. <u>Channel Clearing</u>. (600 feet)

 A 600 foot long area was cleared over 5 days. Logistical, support and personnel needs were underestimated.

B. CHANNEL TREATMENTS.

- 1. Channel Clearing. (2.75 miles)

 2.75 mile riparian area was cleared of floatable debris. Debris was burned on site for increased treatment efficiency and effectiveness. Delay in completion of project due to interruption by fire suppression emergencies in Southern California. Effectiveness monitoring devices established.
- 2. <u>Willow & Straw Wattling.</u> Deleted during final design due to unsuitable sites.
- 3. Gradient Control Log Sills. Deleted during final design due to unsuitable sites.

C. ROAD AND TRAIL TREATMENTS.

- 1. <u>Winter Flood Patrol</u>. Established and utilized as winter storms dictate
- 2. Culvert Clearing. 80 culverts were cleared
- 3. Clearing Ditches. .74 miles of ditches were cleared
- 4. Rip Rap Energy Dissipaters. 500 cu yds energy disipater rip raps were established and determined adequate by final design.
- 5. <u>Debris Racks.</u> 9 debris racks were constructed and installed as determined on site.
- 6. <u>Trail Treatments.</u> Approximately 22 miles of trail within high flood hazard areas were treated.

Road and trail costs were reduced due to efficiency of implementation and final design modifications.

D. OTHER EMERGENCY ACTIONS.

- 1. Road Closure Gates. Three gates were installed as determined by final design.
- 2. <u>Early Warning System</u>. the Forest Service installation of an early warning system in Cachuma Canyon, near the Forest boundary. Operation and maintenance will be by the Santa Barbara County Flood Control District.

E. B.A.E.R EVALUATION AND ADMINISTRATIVE SUPPORT.

1. <u>Team Leaders and Team Members.</u> Approximately 27 people participated in the field and office survey, guided by a 5-person overhead team.

- 2. Archaeology Support. Qualified archaeologists worked with the project layout teams to establish protection measures for known sites, and to post and prescribe protection for subsequently identified sites
- Implementation Overhead. Implementation of project goals required 3. overhead personnel to support operations. Seven people were utilized in records keeping, contracting, project coordination and

Effectiveness	Monitoning To address NEI	PA requirements of evaluating
	actual effectiveness of tre	
estimated vs.	actual effectiveness of the	sacments.
		with the state of
		The second secon
		a nacest
	PART VII - APPROVAL	$\mathbf{\underline{S}}$
. <i>1</i>		- 1 y - 3 .
Forest Superv	igon (Cignotuno)	
Forest Superv	isor (Signature)	Date
. /		
s/		